

EDAS RACONS

4ª Línea de Producción

AGUA BRUTA
TDS : 3.000 ppm

FOULING FACTOR
FF : 0.65

Temp. °C	Cajas 1ªEtap.	Cajas 2ªEtap.	F.C.	Pres. Alim Bar	Pres. Rechaz. Bar	Contrapres. 1ªEtap. Bar	Pres. Booster Bar	Produc. 1ªEtap. m3/hora	Produc. total m3/hora	Caudal ultim membrana		TDS agua Produc.
										1ªEtap.	2ªEtap.	
10	36	12	75	27,68	24,01	7	0	165,54	222,50	4,32	6,85	41,00
12	36	12	75	26,43	22,86	7	0	165,26	222,50	4,32	6,85	44,33
14	36	12	75	25,3	21,83	7	0	165,02	222,50	4,31	6,84	47,63
16	36	12	75	24,26	20,88	7	0	165,00	222,50	4,31	6,84	51,11
18	36	12	75	23,31	20,03	7	0	164,32	222,50	4,32	6,84	54,78
22	36	12	75	21,67	18,55	7	0	163,68	222,50	4,32	6,82	62,75
25	36	12	75	20,61	17,61	7	0	163,11	222,50	4,32	6,81	69,30

